Brand :	**Hitachi**	Running hours :	11958
Type :	KH125-3	Undercarriage:	60%
Serial nr. :	222-1023	Winches :	4
Year of construction :	1990		freefall
Weight :	42500 Kg	Boom length	28m1

URENTELLER
iVEKA
h
11958
Quarz-System

DIMENSIONS OF DISASSEMBLED UNITS FOR TRANSPORTING

(Unit: kg, mm)

Parts name		Weight	Length	Width	Height	Notes
Basic machine	Basic machine	23,900	9,900	3,350	3,175	Included lower boom, Excluded counter wieght
		22,600	6,490	3,350	3,175	Excluded lower boom, ropes, counter wieght
	Counter weight (Inner)	5,800	3,040	590	1,400	
	Counter weight (Outer)	5,800	3,040	440	1,400	
Crane front	Lower boom	600	5,650	1,350	1,400	
	Upper boom	710	4,850	1,350	1,350	
	Back slop	120	4,010	110	130	
	Boom hoist rope	120	1,000	1,000	600	
	Bridle	200	1,250	510	170	
	3 m boom extension	280	3,100	1,350	1,350	
	6 m boom extension	450	6,100	1,350	1,350	
	Jib boom (Upper)	135	3,350	700	550	
	Jib boom (Lower)	125	3,250	600	550	
	3 m jib boom extension	70	3,110	600	550	
	Jib mast	110	3,200	550	560	
	35 t hook	390	1,530	570	340	
	15 t hook	280	1,300	570	290	
	5 t hook	130	770	300	300	

Gewogen 10-10-99 GTD
Transport gewicht met 16 MTR GIEK = 42560 kg